

Validate

Print

Help

PRICE SCHEDULE

(This BOQ template must not be modified/replaced by the bidder and the same should be uploaded after filling the relevent columns, else the bidder is liable to be rejected for this tender. Bidders are allowed to enter the Bidder Name and Values only)

NUMBER #	TEXT #	TEXT #	NUMBER	TEXT #	NUMBER	NUMBER #	TEXT #
S. No.	Item Description	Item Code / Make	Quantity	Units	Estimate d Rate in Rs. P	TOTAL AMOUNT Without Taxes in Rs. P	TOTAL AMOUNT In Words
1	2	3	4	5	6	53	55
2	Earth work in rough excavation, banking excavated earth in layers not exceeding 20cm in depth, breaking clods watering, rolling each layer with ½ tons roller or wooden or steel rammers and rolling every 3rd and top-most layer with power roller of minimum 8 tons and dressing up in embankments for roads, flood banks, marginal banks and guide banks or filling up ground depressions, lead up to 50 m and lift up to 1.5m.	UADD 2012 Building Item no 2.2.1	1963	Cum	182.7	358640.10	INR Three Lakh Fifty Eight Thousand Six Hundred & Forty and Paise Ten Only
3	Providing and laying in position cement concrete of specified grade excluding the cost of centering and shuttering All work up to plinth level (Cement concrete grade M-20 (Nominal Mix) with 20 mm maximum size of stone aggregate)	UADD 2012 Building Item no 4.1.1	508	Cum	4134.6	2100376.80	INR Twenty One Lakh Three Hundred & Seventy Six and Paise Eighty Only
4	Steel work in built up tubular (round, square or rectangular hollow tubes etc.) trusses/frame work etc. including cutting, hoisting, fixing in position and applying a priming coat of approved steel primer, including welding and bolted with special shaped washers etc. complete. (Hot finished welded type tubes)	UADD 2012 Building Item no 10.16.1	284396	Kg	74.7	21244381.20	INR Two Crore Twelve Lakh Forty Four Thousand Three Hundred & Eighty One and Paise Twenty Only
5	Reinforcement for R.C.C. work including straightening, cutting, bending, placing in position and binding all complete. Thermo-Mechanically Treated bars.	UADD 2012 Building Item no 5.20.6	35550	Kg	54	1919700.00	INR Nineteen Lakh Nineteen Thousand Seven Hundred Only
6	Finishing with Epoxy paint (two or more coats) at all locations prepared and applied as per manufacturer's specifications including appropriate priming coat, preparation of surface, etc. complete. On steel work	UADD 2012 Building Item no 13.52.1	13267.00	Sqm.	86.4	1146268.80	INR Eleven Lakh Forty Six Thousand Two Hundred & Sixty Eight and Paise Eighty Only
7	Centering and shuttering including strutting, propping etc.and removal of form for foundations, footings, bases of columns, etc. For mass concrete.	UADD 2012 Building Item no 20.1.1	5000.00	Sqm	124.2	621000.00	INR Six Lakh Twenty One Thousand Only

8	Road Delineators Supplying and installation road delineators (road way indicators), as per MORT&H Clause 806. The structure shall be made in roll forming process having height of 80-100 cm above the ground level, Width not less than 100 mm and shall extend not more than 300mm below the ground while being installed, buried or pressed in to the ground in confirmation with IRC: 79: 1981, are as directed by the by the Engineer painted black with powder coat of minimum 40 microns thickness for protection against corrosion, on top of which Type XI retro reflective sheeting shall be pasted on both sides complying to IRC: 79:1981. The delineator should consist of minimum retro reflective unit exposed area of 330 cm2 white color, full cube corner micro prismatic non-metallic retro reflective sheeting on each side conforming with IRC 67:2012 and meeting the coefficient of retro reflection values as per ASTM D 4956 Type XI table specification. The delineator shall have grooves across the length to make the reflective sheets Vandal- proof.	UADD 2012 Vol-III Road and bridges amedments 01/2018- 19 dated 21-02-2019 Item 8.12	5000.00	Each	1123.2	5616000.00	
9	Road Markers/Road Stud with Lense Reflector Providing and fixing single mould twin shanked molded Road Markers\Road Stud made of poly carbonate or' ABS body and shall support a load of 13635 Kg tested in accordance to ASTM D 4280 and complying to specifications Of Section-5 of and clause 804 of MORTH. As per clause 804.2.2 of MORTH and Section-5 of IRC:35-2015, the reflecting panels shall consist of number of lenses containing single or dual prismatic cubes capable of providing total internal reflection of the light entering the lens face. The slope or retro-reflecting surface should be 35 +/-5 degree to base. The reflective marker shall be fixed to the road surface using the epoxy/ adhesives and the procedure recommended by the manufacturer. No nails shell be used to affix the markers so that they do not pose safety hazard on the road. The contractor shall submit a year replacement warranty for satisfactory field performance including stipulated retro-reflectance of the reflecting panel.	UADD 2012 Vol-III Road and bridges amedments 01/2018- 19 dated 21-02-2019 Item 8.20	130000.00	Each	527.4	68562000.00	INR Six Crore Eighty Five Lakh Sixty Two Thousand Only
Total in Figures						101568366.90	INR Ten Crore Fifteen Lakh Sixty Eight Thousand Three Hundred & Sixty Six and Paise Ninety Only